


1. THE SPLICE ASSEMBLY IS DESIGNED FOR 3" DEEP GRIP STRUT.
2. A 5/8" ϕ HOLE MUST BE FIELD DRILLED IN THE GRIP STRUT FOR INSTALLATION.
3. MATING GRIP STRUT OMITTED FOR CLARITY.



GRIP STRUT FIELD DRILLING DETAIL

ITEM NO.	QTY.	PART NO.	DESCRIPTION
2	2	7000-2162-SP	SPLICE ANGLE, GRIP STRUT, LENGTH 47 3/4"
3	16	4750G-BULK	WASHER, 1/2" NARROW, GALV
4	8	4454G-BULK	1/2" X 1-1/2" A325 GLAV. HEX BOLT
5	8	4754G-BULK	WASHER, 1/2" RGLR LOCK, GALV
6	8	4650G-BULK	NUT, 1/2" HEX, A563 GALV

THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF ALT. ANY REPRODUCTION IN PART OR WHOLE WITHOUT THE WRITTEN PERMISSION OF ALT IS PROHIBITED.

7/10/2017

CAD GENERATED DRAWING,
DO NOT MANUALLY UPDATE



800-950-7933
FAX 940-455-2817
www.advancedlightning.com
sales@advancedlightning.com

122 Leesley Lane
Argyle, Texas
76226

APPROVALS		DATE
DRAWN	JMD	02/15/02
CHECKED	JMD	03/07/02
ENGINEER	JMD	03/07/02
ISSUED	DMR	03/08/02

**ICE BRIDGE GRIP STRUT
SPLICE ASSEMBLY**

DWG. NO. **2162-SP**

SCALE: NTS | DO NOT SCALE DRAWING | SHEET 1 OF 1

REV.
A